

G2 - Alternative 5
Design Warrant

Design Warrant (Appendix G2)

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	CONSTR.	TREATMENT DESCRIPTION ALT5		CLOSURE LEVEL	Cost/mile	ADD-ON Cost	EST. TS COST	SALE SUPPORT ED COST (Incl)	SALE SUPPORTED COST (Add)	BMP FUNDS AVAILABLE	DECOM FUNDS AVAILABLE	ADDITIONAL FUNDS NEEDED
							RECONST AND BEST MGMT PRACTICES										
Alpine Road Decommissioning																	
B01d		18646	1.54	2.12	0.58				6 - 5; full recontour	3800		2204				2204	None
B01d		37146	0	0.2	0.20				6 - 5; full recontour	3800		760				760	None
B01d		37147	0	0.58	0.58				6 - 5; full recontour	3800		2204				2204	None
B01d		37264	0	1.2	1.20				6 - 5; full recontour	3800		4560				4560	None
B02d		37137	0	1.49	1.49				3 - 3s; recont inters, remove cmp	3000		4470				4470	None
B03d		18120	0	1.89	1.89				3 - 3s; recont inters, remove cmp	3000		5670				5670	None
B03d		37260	0	0.6	0.60				3 - 3s; recont inters, remove cmp	3000		1800				1800	None
B03d		37261	0.52	1.86	1.34				3 - 3s; recont inters, remove cmp	3000		4020				4020	None
B03d		37263	0	0.23	0.23				3 - 3s; recont inters, remove cmp	3000		690				690	None
													Source:	TS:	NFN3:		Unknown:
													Available:	0	29600	Needed:	0
													Used:	0	26378		
													Unused:	0	3222		
Landowner Road Decommissioning																	
G01d		37188	0	0.66	0.66				3 - 3s; recont inters, remove cmp	3000		1980				1980	None
G01d		37188	0.66	0.82	0.16				6 - 5; full recontour	3800		608				608	None
G01d		37189	0	0.8	0.80				3 - 3s; recont inters, remove cmp	3000		2400				2400	None
G01d		37190	0.7	1.05	0.35				3 - 3s; recont inters, remove cmp	3000		1050				1050	None
G01d		37191	0	0.8	0.80				3 - 3s; recont inters, remove cmp	3000		2400				2400	None
G01d		37191	0.8	1.33	0.53				5 - 4; recon inters, rip, remove cmp	3300		1749				1749	None
G02d		16937	0	3.9	3.90				3 - 3s; recont inters, remove cmp	3000		11700				11700	None
G02d		37192	0.68	0.98	0.30				3 - 3s; recont inters, remove cmp	3000		900				900	None
G02d		37192	0.98	1.51	0.53				6 - 5; full recontour	3800		2014				2014	None
G02d		37193	0	1.4	1.40				6 - 5; full recontour	3800		5320				5320	None
G02d		37194	0	0.21	0.21				3 - 3s; recont inters, remove cmp	3000		630				630	None
G02d		37196	0	1.18	1.18				3 - 3s; recont inters, remove cmp	3000		3540				3540	None
G02d		37197	0	0.88	0.88				6 - 5; full recontour	3800		3344				3344	None
G02d		37198	0	0.47	0.47				6 - 5; full recontour	3800		1786				1786	None
G02d		37199	0	1.23	1.23				6 - 5; full recontour	3800		4674				4674	None
G02d		37200	0	0.19	0.19				6 - 5; full recontour	3800		722				722	None
G02d		7806	1.56	3.17	1.61				3 - 3s; recont inters, remove cmp	3000		4830				4830	None
G02d		7811	3.11	3.75	0.64				3 - 3s; recont inters, remove cmp	3000		1920				1920	None
G02d		7811	3.75	3.98	0.23				6 - 5; full recontour	3800		874				874	None
G03d		16327	0	2.15	2.15				3 - 3s; recont inters, remove cmp	3000		6450				6450	None
G03d		18578	0	2.43	2.43				3 - 3s; recont inters, remove cmp	3000		7290				7290	None
G03d		37185	0	0.12	0.12				6 - 5; full recontour	3800		456				456	None
G03d		37186	0	0.82	0.82				3 - 3s; recont inters, remove cmp	3000		2460				2460	None
G03d		37187	0	0.97	0.97				6 - 5; full recontour	3800		3686				3686	None
G03d		7782	0	3.06	3.06				3 - 3s; recont inters, remove cmp	3000		9180				9180	None
G03d		7782	3.06	4.52	1.46				6 - 5; full recontour	3800		5548				5548	None
G03d		37350	0	2.19	2.19				3 - 3s; recont inters, remove cmp	3000		6570				6570	None
G04d		37206	0	0.63	0.63				6 - 5; full recontour	3800		2394				2394	None

G2 - Alternative 5
Design Warrant

Design Warrant (Appendix G2)

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	CONSTR.	TREATMENT DESCRIPTION ALT5		Cost/mile	ADD-ON Cost	EST. TS COST	SALE SUPPORT ED COST (Incl)	SALE SUPPORTED COST (Add)	BMP FUNDS AVAILABLE	DECOM FUNDS AVAILABLE	ADDITIONAL FUNDS NEEDED
							RECONST AND BEST MGMT PRACTICES	CLOSURE LEVEL								
	N02d	35106	0	0.49	0.49			6 - 5; full recontour	3800		1862				1862	None
	N02d	35107	0	0.72	0.72			6 - 5; full recontour	3800		2736				2736	None
	N02d	7595	0.69	1.16	0.47			6 - 5; full recontour	3800		1786				1786	None
	N02d	17432	0.64	0.8	0.16			3 - 3s; recont inters, remove cmp	3000		480				480	None
	N02d	17432	0.8	1.56	0.76			6 - 5; full recontour	3800		2888				2888	None
	N02d	35108	0.31	0.8	0.49			6 - 5; full recontour	3800		1862				1862	None
	N02d	35109	0	0.56	0.56			6 - 5; full recontour	3800		2128				2128	None
	N03d	17281	0.58	3.04	2.46			3 - 3s; recont inters, remove cmp	3000		7380				7380	None
	N03d	17282	2.1	2.21	0.11			3 - 3s; recont inters, remove cmp	3000		330				330	None
	N03d	17283	0	2.31	2.31			3 - 3s; recont inters, remove cmp	3000		6930				6930	None
	N03d	18138	0	0.17	0.17			3 - 3s; recont inters, remove cmp	3000		510				510	None
	N04d	18013	1.14	1.32	0.18			3 - 3s; recont inters, remove cmp	3000		540				540	None
	N04d	18117	0.53	0.82	0.29			3 - 3s; recont inters, remove cmp	3000		870				870	None
	N04d	34208	0.22	0.44	0.22			3 - 3s; recont inters, remove cmp	6000		1320				1320	None
	N04d	18104	0.27	0.67	0.40			6 - 5; full recontour	3800		1520				1520	None
	N04d	18115	0	0.34	0.34			3 - 3s; recont inters, remove cmp	3000		1020				1020	None
	N04d	34209	0.42	0.66	0.24			3 - 3s; recont inters, remove cmp	3000		720				720	None
	N04d	34212	0	0.37	0.37			3 - 3s; recont inters, remove cmp	3000		1110				1110	None
	N04d	34267	0	1.13	1.13			6 - 5; full recontour	3800		4294				4294	None
	N04d	34296	0	0.17	0.17			6 - 5; full recontour	3800		646				646	None
	N04d	4219	1.36	1.83	0.47			3 - 3s; recont inters, remove cmp	3000		1410				1410	None
	N04d	4219	1.83	2.36	0.53			6 - 5; full recontour	3800		2014				2014	None
	N05d	16024	0	1.3	1.30			3 - 3s; recont inters, remove cmp	3000		3900				3900	None
	N05d	16060	0	0.49	0.49			6 - 5; full recontour	3800		1862				1862	None
	N05d	16061	0	0.98	0.98			6 - 5; full recontour	3800		3724				3724	None
	N05d	18008	0	2.69	2.69			3 - 3s; recont inters, remove cmp	3000		8070				8070	None
	N05d	18009	0	2.29	2.29			3 - 3s; recont inters, remove cmp	3000		6870				6870	None
	N05d	18102	3.05	4.25	1.20			6 - 5; full recontour	3800		4560				4560	None
	N05d	34016	0	0.91	0.91			3 - 3s; recont inters, remove cmp	3000		2730				2730	None
	N05d	34017	0	0.79	0.79			6 - 5; full recontour	3800		3002				3002	None
	N05d	34048	0	0.14	0.14			3 - 3s; recont inters, remove cmp	3000		420				420	None
	N05d	5501	0	1.21	1.21			6 - 5; full recontour	3800		4598				4598	None
	N06d	16831	0.88	1.63	0.75			3 - 3s; recont inters, remove cmp	3000		2250				2250	None
	N06d	16832	0	0.86	0.86			3 - 3s; recont inters, remove cmp	3000		2580				2580	None
	N06d	16833	0	2.21	2.21			3 - 3s; recont inters, remove cmp	3000		6630				6630	None
	N06d	16837	0	0.27	0.27			3 - 3s; recont inters, remove cmp	3000		810				810	None
	N06d	16838	0	0.38	0.38			3 - 3s; recont inters, remove cmp	3000		1140				1140	None
	N06d	16839	0	0.35	0.35			3 - 3s; recont inters, remove cmp	3000		1050				1050	None
	N06d	16840	0	1.06	1.06			3 - 3s; recont inters, remove cmp	3000		3180				3180	None
	N06d	17284	0	0.79	0.79			3 - 3s; recont inters, remove cmp	3000		2370				2370	None
	N06d	17285	0	1.28	1.28			3 - 3s; recont inters, remove cmp	3000		3840				3840	None
	N06d	17286	0	0.48	0.48			3 - 3s; recont inters, remove cmp	3000		1440				1440	None
	N06d	17288	0	0.6	0.60			3 - 3s; recont inters, remove cmp	3000		1800				1800	None
	N06d	17289	0	0.46	0.46			3 - 3s; recont inters, remove cmp	3000		1380				1380	None
	N06d	17290	0	0.27	0.27			3 - 3s; recont inters, remove cmp	3000		810				810	None

G2 - Alternative 5
Design Warrant

Design Warrant (Appendix G2)

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	CONSTR.	TREATMENT DESCRIPTION ALT5		CLOSURE LEVEL	Cost/mile	ADD-ON Cost	EST. TS COST	SALE SUPPORT ED COST (Incl)	SALE SUPPORTED COST (Add)	BMP FUNDS AVAILABLE	DECOM FUNDS AVAILABLE	ADDITIONAL FUNDS NEEDED
							RECONST AND BEST MGMT PRACTICES										
	N06d	17291	0	1.1	1.10			3 - 3s; recont inters, remove cmp	3000		3300				3300	None	
	N06d	34220	0	0.39	0.39			3 - 3s; recont inters, remove cmp	3000		1170				1170	None	
	N06d	5462	1.35	2.74	1.39			3 - 3s; recont inters, remove cmp	3000		4170				4170	None	
	N06d	Disp. Rec	0	0.06	0.06			6 - 5; full recontour	3800		228				228	None	
	N07d	18010	0	2.94	2.94			3 - 3s; recont inters, remove cmp	3000		8820				8820	None	
	N07d	34014	0	0.9	0.90			3 - 3s; recont inters, remove cmp	3000		2700				2700	None	
	N07d	34015	0	0.38	0.38			6 - 5; full recontour	3800		1444				1444	None	
	N07d	5500	1.91	6.22	4.31			3 - 3s; recont inters, remove cmp	3000		12930				12930	None	
	N07d	5500	6.22	6.78	0.56			6 - 5; full recontour	3800		2128				2128	None	
	N07d	60774	0.9	1.72	0.82			6 - 5; full recontour	3800		3116				3116	None	
S&F	N08d	16058	0	0.54	0.54			3 - 3s; recont inters, remove cmp	3000		1620				1620	None	
	N08d	17233	0.76	3.25	2.49			3 - 3s; recont inters, remove cmp	3000		7470				7470	None	
S&F	N08d	17405	1.1	3.75	2.65			3 - 3s; recont inters, remove cmp	3000		7950				7950	None	
	N08d	34217	0.13	2.53	2.40			3 - 3s; recont inters, remove cmp	3000		7200				7200	None	
	N08d	34217A	0	0.34	0.34			3 - 3s; recont inters, remove cmp	3000		1020				1020	None	
	N08d	34218	0	0.62	0.62			3 - 3s; recont inters, remove cmp	3000		1860				1860	None	
	N08d	34219	0	1.42	1.42			3 - 3s; recont inters, remove cmp	3000		4260				4260	None	
	N08d	5521	3.02	3.68	0.66			3 - 3s; recont inters, remove cmp	3000		1980				1980	None	
	N08d	16025	0	1.41	1.41			3 - 3s; recont inters, remove cmp	3000		4230				4230	None	
	N08d	17403	0	1.68	1.68			6 - 5; full recontour	3800		6384				6384	None	
	N08d	34211	0	0.61	0.61			3 - 3s; recont inters, remove cmp	3000		1830				1830	None	
	N09d	17406	0	0.31	0.31			3 - 3s; recont inters, remove cmp	3000		930				930	None	
S & F	N09d	16353	0	1.6	1.60			3 - 3s; recont inters, remove cmp	3000		4800				4800	None	
S & F perf Lvl III	N09d	16360	0	0.98	0.98			3 - 3s; recont inters, remove cmp	3000		2940				2940	None	
	N09d	17400	0	0.94	0.94			6 - 5; full recontour	3800		3572				3572	None	
	N09d	17401	0	1.63	1.63			3 - 3s; recont inters, remove cmp	3000		4890				4890	None	
	N09d	17402	0	0.84	0.84			6 - 5; full recontour	3800		3192				3192	None	
	N09d	34297	0	0.29	0.29			6 - 5; full recontour	3800		1102				1102	None	
	N10d	34222	0	0.95	0.95			3 - 3s; recont inters, remove cmp	3000		2850				2850	None	
	N10d	16224	0	1.13	1.13			3 - 3s; recont inters, remove cmp	3000		3390				3390	None	
	N10d	16227	0	0.62	0.62			3 - 3s; recont inters, remove cmp	3000		1860				1860	None	
	N10d	16351	0	0.55	0.55			3 - 3s; recont inters, remove cmp	3000		1650				1650	None	
	N10d	16354	0	2.82	2.82			3 - 3s; recont inters, remove cmp	3000		8460				8460	None	
	N10d	16443	0	0.48	0.48			3 - 3s; recont inters, remove cmp	3000		1440				1440	None	
	N10d	16444	0	0.78	0.78			3 - 3s; recont inters, remove cmp	3000		2340				2340	None	
	N10d	16445	2.43	3.07	0.64			3 - 3s; recont inters, remove cmp	3000		1920				1920	None	
	N10d	16446	0	0.46	0.46			3 - 3s; recont inters, remove cmp	3000		1380				1380	None	
	N10d	16535	0	1.18	1.18			3 - 3s; recont inters, remove cmp	3000		3540				3540	None	
	N10d	16835	0	1.86	1.86			3 - 3s; recont inters, remove cmp	3000		5580				5580	None	
	N10d	17292	0	1.53	1.53			3 - 3s; recont inters, remove cmp	3000		4590				4590	None	
	N10d	34018	0	0.61	0.61			3 - 3s; recont inters, remove cmp	3000		1830				1830	None	
	N10d	34019	0	0.47	0.47			3 - 3s; recont inters, remove cmp	3000		1410				1410	None	
	N10d	34020	0	1.36	1.36			3 - 3s; recont inters, remove cmp	3000		4080				4080	None	
	N10d	34022	0	1.13	1.13			3 - 3s; recont inters, remove cmp	3000		3390				3390	None	
	N10d	34023	0	0.95	0.95			3 - 3s; recont inters, remove cmp	3000		2850				2850	None	

G2 - Alternative 5
Design Warrant

Design Warrant (Appendix G2)

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	CONSTR.	TREATMENT DESCRIPTION ALT5		CLOSURE LEVEL	Cost/mile	ADD-ON Cost	EST. TS COST	SALE SUPPORT ED COST (Incl)	SALE SUPPORTED COST (Add)	BMP FUNDS AVAILABLE	DECOM FUNDS AVAILABLE	ADDITIONAL FUNDS NEEDED
							RECONST AND BEST MGMT PRACTICES										
Siegel Road Decommissioning																	
R01d		18260	0	1.01	1.01				3 - 3s; recont inters, remove cmp	3000		3030				0	3030
R01d		18260	1.01	1.42	0.41				3 - 3s; recont inters, remove cmp	3000		1230				0	1230
R01d		35110	0	2.04	2.04				3 - 3s; recont inters, remove cmp	3000		6120				0	6120
R01d		35102	0	0.16	0.16				6 - 5; full recontour	3800		608				0	608
													Source:	TS:	NFN3:		Unknown:
													Available:	0	0	Needed:	10988
													Used:	0	0		
													Unused:	0	0		
Alpine TS Roads To Be Decommissioned																	
alpine		17233	0	0.76	0.76				3 - 3s; recont inters, remove cmp	5000		3806	3806			TS Incl.	None
alpine		17405	0	1.1	1.10				3 - 3s; recont inters, remove cmp			3288	3288			TS Incl.	None
alpine		18121	0	0.43	0.43				3 - 3s; recont inters, remove cmp	6500		2813	2813			TS Incl.	None
alpine		19250	0	1.2	1.20				3 - 3s; recont inters, remove cmp	5000		5952	5952			TS Incl.	None
alpine		20413	0	0.48	0.48				6 - 5; full recontour	7300		3518	3518			TS Incl.	None
alpine		34217	0	0.13	0.13				3 - 3s; recont inters, remove cmp	5000		635	635			TS Incl.	None
													Source:	TS:	NFN3:		Unknown:
													Available:	Included	0	Needed:	0
													Used:	All	0		
													Unused:	0	0		
Thompson Flat TS Roads To Be Decommissioned																	
flat creek		16934	0	0.47	0.47				3 - 3sp; recont inters, remove cmp	5000		2345	2345			TS Incl.	None
flat creek		18684	0	0.61	0.61				3 - 3s; recont inters, remove cmp			3068	3068			TS Incl.	None
flat creek		19252	0	0.79	0.79				3 - 3s; recont inters, remove cmp			3950	3950			TS Incl.	None
flat creek		19253	0	0.74	0.74				3 - 3s; recont inters, remove cmp			4063	4063			TS Incl.	None
flat creek		7873	12.23	12.41	0.18				3 - 3s; recont inters, remove cmp			917	917			TS Incl.	None
flat creek		7880	3.74	4.53	0.79				3 - 3s; recont inters, remove cmp			3934	3934			TS Incl.	None
													Source:	TS:	NFN3:		Unknown:
													Available:	Included	0	Needed:	0
													Used:	All	0		
													Unused:	0	0		
Landowner TS Roads To Be Decommissioned																	
landowner		37190	0	0.7	0.70				3 - 3s; recont inters, remove cmp			4565	NA 4565			0	2100
landowner		37192	0	0.68	0.68				3 - 3s; recont inters, remove cmp	5000		3400	NA 3400			0	2040
landowner		7806	1.55	2.08	0.53				3 - 3s; recont inters, remove cmp			2654	NA 2654			0	1590
landowner		7811	3.01	3.11	0.10				3 - 3s; recont inters, remove cmp			515	NA 515			0	300
													Source:	TS:	NFN3:		Unknown:
													Available:	None	0	Needed:	6030

G2 - Alternative 5
Design Warrant

Design Warrant (Appendix G2)

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	TREATMENT DESCRIPTION ALT5		CLOSURE LEVEL	Cost/mile	ADD-ON Cost	EST. TS COST	SALE SUPPORT ED COST (Incl)	SALE SUPPORTED COST (Add)	BMP FUNDS AVAILABLE	DECOM FUNDS AVAILABLE	ADDITIONAL FUNDS NEEDED
						CONSTR.	RECONST AND BEST MGMT PRACTICES									
												Used:	0	0		
												Unused:	0	0		
Ninemile TS Roads To Be Decommissioned																
ninemile		17281	0	0.58	0.58			3 - 3s; recont inters, remove cmp			3195	3195			TS Incl.	None
ninemile		17282	0	2.1	2.10			3 - 3s; recont inters, remove cmp			13626	13626			TS Incl.	None
ninemile		18013	0	1.14	1.14			3 - 3s; recont inters, remove cmp			7390	7390			TS Incl.	None
ninemile		18103	0	0.1	0.10			5 - 4; recon inters, rip, remove cmp			682	682			TS Incl.	None
ninemile		18104	0	0.27	0.27			6 - 5; full recontour			1566	1566			TS Incl.	None
ninemile		18105	0	0.69	0.69			3 - 3o; recont inters, remove cmp			4565	4565			TS Incl.	None
ninemile		18111	0	0.67	0.67			3 - 3s; recont inters, remove cmp			4366	4366			TS Incl.	None
ninemile		18117	0	0.53	0.53			3 - 3s; recont inters, remove cmp			3455	3455			TS Incl.	None
ninemile		18118	0	0.29	0.29			3 - 3s; recont inters, remove cmp			1865	1865			TS Incl.	None
ninemile		20411	0	0.69	0.69			6 - 5; full recontour			4218	4218			TS Incl.	None
ninemile		20412	0	0.26	0.26			6 - 5; full recontour			1488	1488			TS Incl.	None
ninemile		34208	0	0.22	0.22			3 - 3o; recont inters, remove cmp			1426	1426			TS Incl.	None
ninemile		34209	0	0.42	0.42			3 - 3s; recont inters, remove cmp			2703	2703			TS Incl.	None
ninemile		4219	0	1.36	1.36			3 - 3s; recont inters, remove cmp			8830	8830			TS Incl.	None
ninemile		5472	0	1.82	1.82			3 - 3o; recont inters, remove cmp			15852	15852			TS Incl.	None
												Source:	TS:	NFN3:	Unknown:	
												Available:	Included	0	Needed:	0
												Used:	All	0		
												Unused:	0	0		
Siegel TS Roads To Be Decommissioned																
siegel		17245	0	0.65	0.65			6 - 5; full recontour			4091	4091			TS Incl.	None
siegel		17431	0	0.97	0.97			6 - 5; full recontour			6137	6137			TS Incl.	None
siegel		18139	0	0.57	0.57			6 - 5; full recontour			3592	3592			TS Incl.	None
siegel		35105	0	0.29	0.29			3 - 3o; recont inters, remove cmp			1585	1585			TS Incl.	None
siegel		35108	0	0.31	0.31			6 - 5; full recontour			1798	1798			TS Incl.	None
siegel		7595	0.4	0.69	0.29			6 - 5; full recontour			1676	1676			TS Incl.	None
												Source:	TS:	NFN3:	Unknown:	
												Available:	Included	0	Needed:	0
												Used:	All	0		
												Unused:	0	0		
St. Louis TS Roads To Be Decommissioned																
st louis		17432	0	0.64	0.64			3 - 3s; recont inters, remove cmp			2560	2560			TS Incl.	None
												Source:	TS:	NFN3:	Unknown:	
												Available:	Included	0	Needed:	0
												Used:	All	0		

G2 - Alternative 5
Design Warrant

Design Warrant (Appendix G2)

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	CONSTR.	TREATMENT DESCRIPTION ALTS		CLOSURE LEVEL	Cost/mile	ADD-ON Cost	EST. TS COST	SALE SUPPORT ED COST (Incl)	SALE SUPPORTED COST (Add)	BMP FUNDS AVAILABLE	DECOM FUNDS AVAILABLE	ADDITIONAL FUNDS NEEDED
							RECONST AND BEST MGMT PRACTICES										
												Unused:	0	0			
Alpine Road BMP Implementation																	
	B01	7893	0	2.77	2.77		yes		12500		34625			15200		19425	
alpine alt	B01	283	0.55	1.56	1.01		yes		7500	50000	57575	707	56868	0		None	
alpine	B02	536	8.75	13.72	4.97		yes		11200		55657	3479	52178	0		None	
alpine alt	B02	536	0	8.75	8.75		yes		12500		109375	6125	103250	0		None	
	B03	18570	0	1.02	1.02		yes		6000		6120		0	0		6120	
	B03	18571	0	2.7	2.70		yes		6000		16200		0	0		16200	
	B04	18749	0	2.05	2.05		yes		6000		12300		0	0		12300	
	B04	37149	0	1.3	1.30		yes		6000		7800		0	0		7800	
	B05	19250	2.7	2.71	0.01		yes		6000		60		0	0		60	
	B05	37257	0	0.09	0.09		yes		6000		540		0	0		540	
	B05	37257	0.41	0.44	0.03		yes		6000		180		0	0		180	
	B05	16956	0	0.23	0.23		yes		9500		2185		0	0		2185	
	B05	18746	1.21	1.56	0.35		yes		6000		2100		0	0		2100	
	B05	18748	0	2.21	2.21		yes		6000		13260		0	0		13260	
	B05	37133	0.18	0.22	0.04		yes		6000		240		0	0		240	
	B05	37133	0.4	0.57	0.17		yes		6000		1020		0	0		1020	
	B05	37153	0.45	0.54	0.09		yes		6000		540		0	0		540	
	B05	37154	0	0.2	0.20		yes		6000		1200		0	0		1200	
	B05	37169	0.09	0.13	0.04		yes		6000		240		0	0		240	
	B05	7892	11.01	11.029	0.02		yes		8500		170		0	0		170	
												Source:	TS:	NFN3:		Unknown:	
												Available:	802000	15200	Needed:	83580	
												Used:	281555	15200			
												Unused:	520445	0			
Landowner Road BMP Implementation																	
landowner	G01,G03,G10	250	83.066	95.86	12.79		yes				222417	9673 NA	0	93600		128817	
	G02	18577	0.17	2.17	2.00		yes		6000		12000		0	0		12000	
landowner	G02	18577	0	0.17	0.17		yes				2244	425 NA	0	0		2244	
landowner	G04	7811	0	3.01	3.01		yes				39681	2104 NA	0	0		39681	
	G05	16169	0.87	2.44	1.57		yes		9500		14915		0	0		14915	
landowner	G05	16169	0	0.87	0.87		yes		7500		6525		0	0		6525	
	G06	450	5.58	9.56	3.98		yes		11000		43780		0	0		43780	
landowner	G06	450	0	5.58	5.58		yes				65335	3910 NA	0	0		65335	
	G07	388	1.07	5.21	4.14		yes		12500		51750		0	0		51750	
	G08	7813	0	1.95	1.95		yes		12500		24375		0	0		24375	
	G09	7812	0	5.53	5.53		yes		12500		69125		0	0		69125	
	G10	250	95.86	101.96	6.10		yes		12500		76250		0	0		76250	
	G11	7798	0	12.13	12.13		yes		12500		151625		0	0		151625	
	G12	18533	0	3.38	3.38		yes		6000		20280		0	0		20280	

G2 - Alternative 5
Design Warrant

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	TREATMENT DESCRIPTION ALT5		CLOSURE LEVEL	Cost/mile	ADD-ON Cost	EST. TS COST	SALE SUPPORT ED COST (Incl)	SALE SUPPORTED COST (Add)	BMP FUNDS AVAILABLE	DECOM FUNDS AVAILABLE	ADDITIONAL FUNDS NEEDED
						CONSTR.	RECONST AND BEST MGMT PRACTICES									
	G14	37195	0	1.11	1.11		yes		6000		6660		0	0		6660
	G14	7806	0	1.56	1.56		yes		12500		19500		0	0		19500
landowner	G14	7806	0	1.55	1.55		yes				20483	1086 NA	0	0		20483
	G16	7789	10.32	10.42	0.10		yes		12500		1250		0	0		1250
	G17	37225	0	0.03	0.03		yes		6000		180		0	0		180
	G17	37307	0	0.1	0.10		yes		6000		600		0	0		600
	G17	5428-2	7.86	7.97	0.11		yes		12500		1375		0	0		1375
	G17	5428-4	8.41	9.44	1.03		yes		12500		12875		0	0		12875
	G17	7819	0	2.44	2.44		yes		12500		30500		0	0		30500
landowner	G17	5560	0	1.47	1.47		yes				17249	1032 NA	0	0		17249
	G18	37184	0	0.36	0.36		yes		6000		2160		0	0		2160
	G18	553	0	0.56	0.56		yes		12500		7000		0	0		7000
	G18	7803	0	2.51	2.51		yes		11000		27610		0	0		27610
												Source:	TS:	NFN3:		Unknown:
												Available:	0	93600	Needed:	854144
												Used:	0	93600		
												Unused:	0	0		
Ninemile Road BMP Implementation																
st louis	N01	5498	8.65	10.54	1.89		yes			70000	132828	1305	11000	110400		10123
	N02	412	17.43	20.36	2.93		yes	1 - 1; J restriction	30900	8000	98634		0	0		98634
ninemile	N03	5498	0	8.65	8.65		yes				380938	6052	0	0		374,886
	N04	412	15.56	17.43	1.87		yes		40900	40000	116483		0	0		116483
ninemile	N04	412	10.17	15.56	5.39		yes				187787	3801 (p) 5000	0	0		178,986
	N04,N16	16831	0	0.88	0.88		yes		12500	15000	25993		0	0		25993
	N04,N16	4256	0	2.14	2.14		yes		12500	30000	56750		0	0		56750
	N05	18102	0	3.05	3.05		yes	1 - 1; E restriction	6000		18300		0	0		18300
	N06	5500	1.73	1.91	0.18		yes		7500		1350		0	0		1350
pine creek	N06	5500	0	1.73	1.73		yes				14070	1201	0	0		12869
	N07	97	1.41	4.29	2.88		yes	1 - 1; E restriction	8000		23040		0	0		23040
	N07	97	4.29	9.77	5.48		yes		8000		43840		0	0		43840
	N08	5520	18.42	22.6	4.18		yes		12500		52250		0	0		52250
alpine	N08	5520	15.73	18.45	2.72		yes				65943	1907	64036	0		None
alpine	N09	5475	0	5.02	5.02		yes				5711	488	5223	0		None
	N10	5520	5.46	15.7	10.24		yes		12500	85000	213000		0	0		213000
	N12	5572	3.09	5.72	2.63		yes		7500		19725		0	0		19275
	N12	18157	0	2.11	2.11		yes		9500		20045		0	0		20045
siegel	N12	5572	0	3.09	3.09		yes		8200		25338	2163	23175	0		None
siegel	N12	7595	0	0.4	0.40		yes				1400	1400	0	0		None
	N14	5499	0	0.11	0.11		yes		3500		385		0	0		385
	N16	34221	0	0.54	0.54		yes		6000		3240		0	0		3240
	N16	5462	0	1.35	1.35		yes		12500		16875		0	0		16875
	N17	16516	1.54	1.6	0.06		yes		6000		360		0	0		360
	N17	17246	0	0.41	0.41		yes		3500		1435		0	0		1435
	N17	17248	0.7	1.87	1.17		yes		12500		14625		0	0		14625

G2 - Alternative 5
Design Warrant

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	TREATMENT DESCRIPTION ALT5		CLOSURE LEVEL	Cost/mile	ADD-ON Cost	EST. TS COST	SALE SUPPORT ED COST (Incl)	SALE SUPPORTED COST (Add)	BMP FUNDS AVAILABLE	DECOM FUNDS AVAILABLE	ADDITIONAL FUNDS NEEDED
						CONSTR.	RECONST AND BEST MGMT PRACTICES									
	N17	5503	0	1.11	1.11		yes		6000		6660		0	0		6660
	N18	5521	0	3.02	3.02		yes		12500		37750		0	0		37750
	N20	16223	0	2.08	2.08		yes		9500		19760		0	0		19760
	N20	16445	0	2.43	2.43		yes		6000		14580		0	0		14580
	N20	16762	0	0.92	0.92		yes		6000		5520		0	0		5520
	N20	18166	0	0.12	0.12		yes		6000		720		0	0		720
	N20	5518	0	2.66	2.66		yes		12500		33250		0	0		33250
	N20	9955	1.71	2.25	0.54		yes		11000		5940		0	0		5940
	N21	9920	1.78	5.479	3.70		yes	1 - 1; J restriction	2000		7398		0	0		7398
st louis	N21	9920	0	1.78	1.78		yes	1 - 1; J restriction			3476	3476	0	0		None
												Source:	TS:	NFN3:	Unknown:	
												Available:	sl 11000	110400	Needed:	1434322
													pine 5000			
													alp 69259			
													sg 23175			
												Used:	108434	110400		
												Unused:	0	0		
Thompson Flat Road BMP Implementation																
flat creek	P01	540	0	3.14	3.14		yes		13200	25000	66448	2198	64250	0		None
	P02	540	3.14	9.09	5.95		yes		12500		74375		0	74375		None
flat creek	P03	7882	0	4.1	4.10		yes		13200	30000	84120	2870	81250	0		None
flat creek	P04	7757	0	1.38	1.38		yes				11727	966	10761	0		None
flat creek	P04	7873	0	12.23	12.23		yes				118627	8560	110067	0		None
	P05	194	3.31	6.25	2.94		yes		9000		26460		0	26460		None
flat creek	P05	194	0.43	3.31	2.88		yes				27889	2013	25876	0		None
	P06	18740	0	0.95	0.95		yes		6000		5700		0	1565		4135
	P06	18741	0	1.82	1.82		yes		6000		10920		0	0		10920
	P06	37121	0	0.23	0.23		yes		6000		1380		0	0		1380
	P07	16972	0	0.89	0.89		yes		6000		5340		0	0		5340
	P07	16973	0	0.88	0.88		yes		6000		5280		0	0		5280
	P07	18515	0	1.14	1.14		yes		6000		6840		0	0		6840
	P07	18742	0	0.78	0.78		yes		6000		4680		0	0		4680
flat creek	P07	7880	0	3.74	3.74		yes				26919	2617	24302	0		None
	P08	18714	0	1.4	1.40		yes		6000		8400		0	0		8400
	P08	27000	0	0.28	0.28		yes		6000		1680		0	0		1680
	P08	7871	0	3.77	3.77		yes		9000		33930		0	0		33930
	P08	7871	4.87	7.02	2.15		yes		9000		19350		0	0		19350
	P08	7872	0	4.17	4.17		yes		9000		37530		0	0		37530
flat creek	P08	47039	0	0.59	0.59		yes		8200		4892	4892	0	0		None
flat creek	P08	16976	0	1.11	1.11		yes		9700		10786	2780	8006	0		None
	P09	7870	0.71	3.21	2.50		yes		9000		22500		0	0		22500
	P10	18739	0.52	0.91	0.39		yes		2800		1092		0	0		1092
flat creek	P10	18739	0	0.52	0.52		yes				1827	1827	0	0		None
	P11	16974	0	2.12	2.12		yes		6000		12720		0	0		12720

G2 - Alternative 5
Design Warrant

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	FUNDING SOURCE	IMPLEMENTATION RESPONSIBILITY				SPECIAL DESIGN CONSIDERATIONS			
							SURVEY	DESIGN	ADMIN	CONSTR.	PRIORITY CULVERTS	HAUL ROUTE	SALE YEAR PLANNED	IMPL YEAR
	N02d	35106	0	0.49	0.49	NFN3	Contract	Contract	USFS	Contract		no		2003
	N02d	35107	0	0.72	0.72	NFN3	Contract	Contract	USFS	Contract		no		2003
	N02d	7595	0.69	1.16	0.47	NFN3	Contract	Contract	USFS	Contract		no		2003
	N02d	17432	0.64	0.8	0.16	NFN3	Contract	Contract	USFS	Contract		no		2004
	N02d	17432	0.8	1.56	0.76	NFN3	Contract	Contract	USFS	Contract		no		2004
	N02d	35108	0.31	0.8	0.49	NFN3	Contract	Contract	USFS	Contract		no		2004
	N02d	35109	0	0.56	0.56	NFN3	Contract	Contract	USFS	Contract		no		2004
	N03d	17281	0.58	3.04	2.46	NFN3	Contract	Contract	USFS	Contract		no		2003
	N03d	17282	2.1	2.21	0.11	NFN3	Contract	Contract	USFS	Contract		no		2003
	N03d	17283	0	2.31	2.31	NFN3	Contract	Contract	USFS	Contract		no		2005
	N03d	18138	0	0.17	0.17	NFN3	Contract	Contract	USFS	Contract		no		2005
	N04d	18013	1.14	1.32	0.18	NFN3	Contract	Contract	USFS	Contract		no		2003
	N04d	18117	0.53	0.82	0.29	NFN3	Contract	Contract	USFS	Contract		no		2003
	N04d	34208	0.22	0.44	0.22	NFN3	Contract	Contract	USFS	Contract		no		2003
	N04d	18104	0.27	0.67	0.40	NFN3	Contract	Contract	USFS	Contract		no		2004
	N04d	18115	0	0.34	0.34	NFN3	Contract	Contract	USFS	Contract		no		2004
	N04d	34209	0.42	0.66	0.24	NFN3	Contract	Contract	USFS	Contract		no		2004
	N04d	34212	0	0.37	0.37	NFN3	Contract	Contract	USFS	Contract		no		2004
	N04d	34267	0	1.13	1.13	NFN3	Contract	Contract	USFS	Contract		no		2004
	N04d	34296	0	0.17	0.17	NFN3	Contract	Contract	USFS	Contract		no		2004
	N04d	4219	1.36	1.83	0.47	NFN3	Contract	Contract	USFS	Contract		no		2004
	N04d	4219	1.83	2.36	0.53	NFN3	Contract	Contract	USFS	Contract		no		2004
	N05d	16024	0	1.3	1.30	NFN3	Contract	Contract	USFS	Contract	no	no		2008
	N05d	16060	0	0.49	0.49	NFN3	Contract	Contract	USFS	Contract		no		2008
	N05d	16061	0	0.98	0.98	NFN3	Contract	Contract	USFS	Contract		no		2008
	N05d	18008	0	2.69	2.69	NFN3	Contract	Contract	USFS	Contract		no		2008
	N05d	18009	0	2.29	2.29	NFN3	Contract	Contract	USFS	Contract		no		2008
	N05d	18102	3.05	4.25	1.20	NFN3	Contract	Contract	USFS	Contract		no		2008
	N05d	34016	0	0.91	0.91	NFN3	Contract	Contract	USFS	Contract		no		2008
	N05d	34017	0	0.79	0.79	NFN3	Contract	Contract	USFS	Contract		no		2008
	N05d	34048	0	0.14	0.14	NFN3	Contract	Contract	USFS	Contract		no		2008
	N05d	5501	0	1.21	1.21	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	16831	0.88	1.63	0.75	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	16832	0	0.86	0.86	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	16833	0	2.21	2.21	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	16837	0	0.27	0.27	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	16838	0	0.38	0.38	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	16839	0	0.35	0.35	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	16840	0	1.06	1.06	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	17284	0	0.79	0.79	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	17285	0	1.28	1.28	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	17286	0	0.48	0.48	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	17288	0	0.6	0.60	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	17289	0	0.46	0.46	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	17290	0	0.27	0.27	NFN3	Contract	Contract	USFS	Contract		no		2008

G2 - Alternative 5
Design Warrant

Design Warrant (Appendix G2)

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	FUNDING SOURCE	IMPLEMENTATION RESPONSIBILITY				SPECIAL DESIGN CONSIDERATIONS			
							SURVEY	DESIGN	ADMIN	CONSTR.	PRIORITY CULVERTS	HAUL ROUTE	SALE YEAR PLANNED	IMPL YEAR
	N06d	17291	0	1.1	1.10	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	34220	0	0.39	0.39	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	5462	1.35	2.74	1.39	NFN3	Contract	Contract	USFS	Contract		no		2008
	N06d	Disp. Rec	0	0.06	0.06	NFN3	Contract	Contract	USFS	Contract		no		2008
	N07d	18010	0	2.94	2.94	NFN3	Contract	Contract	USFS	Contract		no		2002
	N07d	34014	0	0.9	0.90	NFN3	Contract	Contract	USFS	Contract		no		2002
	N07d	34015	0	0.38	0.38	NFN3	Contract	Contract	USFS	Contract		no		2002
	N07d	5500	1.91	6.22	4.31	NFN3	Contract	Contract	USFS	Contract		no		2002
	N07d	5500	6.22	6.78	0.56	NFN3	Contract	Contract	USFS	Contract		no		2002
	N07d	60774	0.9	1.72	0.82	NFN3	Contract	Contract	USFS	Contract		no		2002
S&F	N08d	16058	0	0.54	0.54	NFN3	Contract	Contract	USFS	Contract		no		2006
	N08d	17233	0.76	3.25	2.49	NFN3	Contract	Contract	USFS	Contract		no		2006
S&F	N08d	17405	1.1	3.75	2.65	NFN3	Contract	Contract	USFS	Contract		no		2006
	N08d	34217	0.13	2.53	2.40	NFN3	Contract	Contract	USFS	Contract		no		2006
	N08d	34217A	0	0.34	0.34	NFN3	Contract	Contract	USFS	Contract		no		2006
	N08d	34218	0	0.62	0.62	NFN3	Contract	Contract	USFS	Contract		no		2006
	N08d	34219	0	1.42	1.42	NFN3	Contract	Contract	USFS	Contract		no		2006
	N08d	5521	3.02	3.68	0.66	NFN3	Contract	Contract	USFS	Contract		no		2006
	N08d	16025	0	1.41	1.41	NFN3	Contract	Contract	USFS	Contract		no		2008
	N08d	17403	0	1.68	1.68	NFN3	Contract	Contract	USFS	Contract		no		2008
	N08d	34211	0	0.61	0.61	NFN3	Contract	Contract	USFS	Contract		no		2008
	N09d	17406	0	0.31	0.31	NFN3	Contract	Contract	USFS	Contract		no		2004
S & F	N09d	16353	0	1.6	1.60	NFN3	Contract	Contract	USFS	Contract		no		2006
S & F perf Lvl III	N09d	16360	0	0.98	0.98	NFN3	Contract	Contract	USFS	Contract		no		2006
	N09d	17400	0	0.94	0.94	NFN3	Contract	Contract	USFS	Contract		no		2008
	N09d	17401	0	1.63	1.63	NFN3	Contract	Contract	USFS	Contract		no		2008
	N09d	17402	0	0.84	0.84	NFN3	Contract	Contract	USFS	Contract		no		2008
	N09d	34297	0	0.29	0.29	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	34222	0	0.95	0.95	NFN3	Contract	Contract	USFS	Contract		no		2004
	N10d	16224	0	1.13	1.13	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16227	0	0.62	0.62	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16351	0	0.55	0.55	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16354	0	2.82	2.82	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16443	0	0.48	0.48	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16444	0	0.78	0.78	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16445	2.43	3.07	0.64	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16446	0	0.46	0.46	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16535	0	1.18	1.18	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	16835	0	1.86	1.86	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	17292	0	1.53	1.53	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	34018	0	0.61	0.61	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	34019	0	0.47	0.47	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	34020	0	1.36	1.36	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	34022	0	1.13	1.13	NFN3	Contract	Contract	USFS	Contract		no		2008
	N10d	34023	0	0.95	0.95	NFN3	Contract	Contract	USFS	Contract		no		2008

G2 - Alternative 5
Design Warrant

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	FUNDING SOURCE	IMPLEMENTATION RESPONSIBILITY				SPECIAL DESIGN CONSIDERATIONS			
							SURVEY	DESIGN	ADMIN	CONSTR.	PRIORITY CULVERTS	HAUL ROUTE	SALE YEAR PLANNED	IMPL YEAR
Siegel Road Decommissioning														
R01d		18260	0	1.01	1.01	Unknown	Contract	Contract	USFS	Contract		no		2008
R01d		18260	1.01	1.42	0.41	Unknown	Contract	Contract	USFS	Contract		no		2002
R01d		35110	0	2.04	2.04	Unknown	Contract	Contract	USFS	Contract		no		2002
R01d		35102	0	0.16	0.16	Unknown	Contract	Contract	USFS	Contract		no		2003
Alpine TS Roads To Be Decommissioned														
alpine		17233	0	0.76	0.76	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
alpine		17405	0	1.1	1.10	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
alpine		18121	0	0.43	0.43	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
alpine		19250	0	1.2	1.20	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
alpine		20413	0	0.48	0.48	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
alpine		34217	0	0.13	0.13	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
Thompson Flat TS Roads To Be Decommissioned														
flat creek		16934	0	0.47	0.47	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2004
flat creek		18684	0	0.61	0.61	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2004
flat creek		19252	0	0.79	0.79	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
flat creek		19253	0	0.74	0.74	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
flat creek		7873	12.23	12.41	0.18	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
flat creek		7880	3.74	4.53	0.79	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
Landowner TS Roads To Be Decommissioned														
landowner		37190	0	0.7	0.70	Unknown	USFS.	USFS.	USFS.	Purch	no	yes	2004	2003
landowner		37192	0	0.68	0.68	Unknown	USFS.	USFS.	USFS.	Purch			2004	
landowner		7806	1.55	2.08	0.53	Unknown	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
landowner		7811	3.01	3.11	0.10	Unknown	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004

G2 - Alternative 5
Design Warrant

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	FUNDING SOURCE	IMPLEMENTATION RESPONSIBILITY				SPECIAL DESIGN CONSIDERATIONS			
							SURVEY	DESIGN	ADMIN	CONSTR.	PRIORITY CULVERTS	HAUL ROUTE	SALE YEAR PLANNED	IMPL YEAR
Ninemile TS Roads To Be Decommissioned														
ninemile		17281	0	0.58	0.58	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
ninemile		17282	0	2.1	2.10	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
ninemile		18013	0	1.14	1.14	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
ninemile		18103	0	0.1	0.10	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
ninemile		18104	0	0.27	0.27	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
ninemile		18105	0	0.69	0.69	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
ninemile		18111	0	0.67	0.67	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
ninemile		18117	0	0.53	0.53	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
ninemile		18118	0	0.29	0.29	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
ninemile		20411	0	0.69	0.69	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
ninemile		20412	0	0.26	0.26	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
ninemile		34208	0	0.22	0.22	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
ninemile		34209	0	0.42	0.42	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
ninemile		4219	0	1.36	1.36	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
ninemile		5472	0	1.82	1.82	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
Siegel TS Roads To Be Decommissioned														
siegel		17245	0	0.65	0.65	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2003
siegel		17431	0	0.97	0.97	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
siegel		18139	0	0.57	0.57	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2003
siegel		35105	0	0.29	0.29	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2003	2003
siegel		35108	0	0.31	0.31	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004
siegel		7595	0.4	0.69	0.29	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2003
St. Louis TS Roads To Be Decommissioned														
st louis		17432	0	0.64	0.64	TS Incl.	USFS.	USFS.	USFS.	Purch	no	yes	2004	2004

G2 - Alternative 5
Design Warrant

Design Warrant (Appendix G2)

TS NAME	PRIORITY	ROAD NUMBER	BOP	EOP	MILES	FUNDING SOURCE	IMPLEMENTATION RESPONSIBILITY				SPECIAL DESIGN CONSIDERATIONS				
							SURVEY	DESIGN	ADMIN	CONSTR.	PRIORITY CULVERTS	HAUL ROUTE	SALE YEAR PLANNED	IMPL YEAR	
Alpine Road BMP Implementation															
	B01	7893	0	2.77	2.77	NFN3,unk							no		2004
alpine alt	B01	283	0.55	1.56	1.01	TS					Purch		yes	2002	
alpine	B02	536	8.75	13.72	4.97	TS	USFS.	USFS.	USFS.	Purch	no	yes	2002		
alpine alt	B02	536	0	8.75	8.75	TS				Purch		yes	2002		
	B03	18570	0	1.02	1.02	Unknown	Contract	Contract	USFS	Contract		no			2004
	B03	18571	0	2.7	2.70	Unknown	Contract	Contract	USFS	Contract		no			2004
	B04	18749	0	2.05	2.05	Unknown	Contract	Contract	USFS	Contract		no			2004
	B04	37149	0	1.3	1.30	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	19250	2.7	2.71	0.01	Unknown	Contract	Contract	USFS	Contract		no			2003
	B05	37257	0	0.09	0.09	Unknown	Contract	Contract	USFS	Contract		no			2003
	B05	37257	0.41	0.44	0.03	Unknown	Contract	Contract	USFS	Contract		no			2003
	B05	16956	0	0.23	0.23	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	18746	1.21	1.56	0.35	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	18748	0	2.21	2.21	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	37133	0.18	0.22	0.04	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	37133	0.4	0.57	0.17	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	37153	0.45	0.54	0.09	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	37154	0	0.2	0.20	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	37169	0.09	0.13	0.04	Unknown	Contract	Contract	USFS	Contract		no			2004
	B05	7892	11.01	11.029	0.02	Unknown	Contract	Contract	USFS	Contract		no			2004
Landowner Road BMP Implementation															
landowner	G01,G03,G10	250	83.066	95.86	12.79	NFN3,unk	USFS.	USFS.	USFS.	Purch	yes	yes	2002	2003	
	G02	18577	0.17	2.17	2.00	Unknown	Contract	Contract	USFS	Contract		no			2008
landowner	G02	18577	0	0.17	0.17	Unknown	USFS.	USFS.	USFS.	Purch	no	yes	2003	2008	
landowner	G04	7811	0	3.01	3.01	Unknown	USFS.	USFS.	USFS.	Purch	no	yes	2003	2004	
	G05	16169	0.87	2.44	1.57	Unknown	Contract.	Contract.	USFS.	Contract.		no			2004
landowner	G05	16169	0	0.87	0.87	Unknown	USFS.	USFS.	USFS.	Purch	no		2002	2004	
	G06	450	5.58	9.56	3.98	Unknown	Contract	Contract	USFS	Contract		no			2003
landowner	G06	450	0	5.58	5.58	Unknown	USFS.	USFS.	USFS.	Purch	yes	yes	2002	2003	
	G07	388	1.07	5.21	4.14	Unknown	Contract	Contract	USFS	Contract		no			2008
	G08	7813	0	1.95	1.95	Unknown	Contract	Contract	USFS	Contract		no			2008
	G09	7812	0	5.53	5.53	Unknown	Contract	Contract	USFS	Contract		no			2008
	G10	250	95.86	101.96	6.10	Unknown	Contract.	Contract.	USFS.	Contract.		no			2003
	G11	7798	0	12.13	12.13	Unknown	Contract	Contract	USFS	Contract		no			2008
	G12	18533	0	3.38	3.38	Unknown	Contract	Contract	USFS	Contract		no			2008

